	Item Name	Unit	Estimate Quantity	Rates quoted by Sri.C N S MURTHY	
				Rate in figures	Rate in words
203	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete. 14SWG ---- All terms and conditions are as per Tender Document	sq.cms	5000.00	0.40	Rupees And Paise Forty Only
204	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia ---- All terms and conditions are as per Tender Document	No	2.00	2945.00	Rupees Two Thousand Nine Hundred Forty Five Only
205	Supplying fixing and wiring earth electrode for grounding of lifts, transformers, DG sets etc. using 40mm dia 2.9mm thick 2.5 mtr long GI pipe with GI funnel with mesh and suitable size reducer fixed on the top of the earth electrode. The funnel should be enclosed in a CC chamber of 400x400x400mm with a cast iron cover. The earth electrode shall have staggered holes of 12mm dia and the electrode should be covered 150mm all-round with alternate layers of salt and charcoal from the bottom of the CC chamber. The connection from the electrode is to be established through GI strip using GI bolts and nuts. ---- All terms and conditions are as per Tender Document	No	2.00	4662.00	Rupees Four Thousand Six Hundred Sixty Two Only
206	Supplying and running of GI/Copper strips for grounding connections, using necessary fixing materials as required. GI strip 25x3mm ---- All terms and conditions are as per Tender Document	Mtr	20.00	83.00	Rupees Eighty Three Only
207	600x600x3mm GI Plate ---- All terms and conditions are as per Tender Document	Each	4.00	847.00	Rupees Eight Hundred Forty Seven Only
208	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A. 4 core 10 sqmm ---- All terms and conditions are as per Tender Document	Mtr	15.00	127.00	Rupees One Hundred Twenty Seven Only
209	4 core 16 sqmm ---- All terms and conditions are as per Tender Document	Mtr	10.00	151.00	Rupees One Hundred Fifty One Only
210	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.On wall /Structure 6 sqmm to 16 sqmm ---- All terms and conditions are as per Tender Document	Mtr	30.00	33.00	Rupees Thirty Three Only
211	25 sqmm to 75 sqmm ---- All terms and conditions are as per Tender Document	Mtr	150.00	37.00	Rupees Thirty Seven Only
212	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete.In soil (ordinary) ---- All terms and conditions are as per Tender Document	Mtr	30.00	86.00	Rupees Eighty Six Only
213	Asphalt cutting ---- All terms and conditions are as per Tender Document	Mtr	5.00	125.00	Rupees One Hundred Twenty Five Only
214	Providing and filling sand in excavated trench to cover already laid UG cable to a depth of 150mm all-round the cable. ---- All terms and conditions are as per Tender Document	Mtr	30.00	111.00	Rupees One Hundred Eleven Only
215	Supplying and fixing of heavy duty cable glands suitable for UG cable of 1.1 KV class (metal only) 25mm dia ---- All terms and conditions are as per Tender Document	Each	2.00	93.00	Rupees Ninety Three Only

Executive Engineer
Project Division
Yelahanka Zone

Contractor

	Item Name	Unit	Estimate Quantity	Rates quoted by Sri.C N S MURTHY	
				Rate in figures	Rate in words
	32mm dia ---- All terms and conditions are as per Tender Document	Each	2.00	132.00	Rupees One Hundred Thirty Two Only
217	Supplying and fixing 2mm thick perforated cable tray with powder coated paint on existing MS angle support using necessary GI bolts/nuts and washer or welding as required 300x50mm ---- All terms and conditions are as per Tender Document	Mtr	5.00	590.00	Rupees Five Hundred Ninety Only
218	Supply and laying double walled corrugated (DWC) HDPE Pipe including all necessary connecting Sockets/Couplings/Tees/Bends/End-caps of same materials in existing trench as per IS 14930 part -II suitable for drawing underground cables. 40mm OD / 32mm ID ---- All terms and conditions are as per Tender Document	Mtr	50.00	106.00	Rupees One Hundred Six Only
219	50mm OD / 38mm ID ---- All terms and conditions are as per Tender Document	Mtr	40.00	163.00	Rupees One Hundred Sixty Three Only
220	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes. 1.5 sqmm ---- All terms and conditions are as per Tender Document	Each	30.00	3.00	Rupees Three Only
221	2.5 sqmm ---- All terms and conditions are as per Tender Document	Each	20.00	4.00	Rupees Four Only
222	4 sqmm ---- All terms and conditions are as per Tender Document	Each	10.00	7.00	Rupees Seven Only
223	6 sqmm ---- All terms and conditions are as per Tender Document	Each	8.00	7.00	Rupees Seven Only
224	10 sqmm ---- All terms and conditions are as per Tender Document	Each	15.00	9.00	Rupees Nine Only
225	16 sqmm ---- All terms and conditions are as per Tender Document	Each	4.00	13.00	Rupees Thirteen Only
226	35 sqmm Long Barrel ---- All terms and conditions are as per Tender Document	Each	4.00	37.00	Rupees Thirty Seven Only
227	Supplying and running GI/Copper conductor for grounding and (along with other wires in conduit system of wiring) using necessary suitable size clamps, nails, guttas/spacers etc. GI Wire 8 SWG ---- All terms and conditions are as per Tender Document	Mtr	50.00	21.00	Rupees Twenty One Only
228	Supplying and drawing PVC flexible one pair telephone unarmoured tinned copper cable. 2Pair ---- All terms and conditions are as per Tender Document	Rmt.	50.00	15.00	Rupees Fifteen Only
229	Constructing brick masonry inspection chamber 600x600mm and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non- modular bricks of class designation 50 in cement mortar 1:5, C.I cover with frame (light duty) 455x610mm internal dimensions, total weight of cover with frame to be not less than 38kg (weight of cover 23kg and weight of frame 15kg) R.C.C top slab with cement concrete M 15 with 20mm and down size granite metal, foundation concrete M5 with 40mm and down size granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, HOM of machineries complete as per specifications. Specification no. KBS --- All terms and conditions are as per Tender Document	Nos	2.00	10443.00	Rupees Ten Thousand Four Hundred Forty Three Only
230	Providing and fixing unplasticised PVC pipes 10.00 kg/sq.cm working pressure chemp plast/wavin or equivalent make with pipe fittings, clips, making good the floor , including cost of all materials, labour charges, HOM of equipment and testing complete as per specifications. do- with 90mm outer dia ---- All terms and conditions are as per Tender Document	m	20.00	560.00	Rupees Five Hundred Sixty Only
231	with 110mm outer dia ---- All terms and conditions are as per Tender Document	m	13.00	802.00	Rupees Eight Hundred Two Only
232	with 160mm outer dia ---- All terms and conditions are as per Tender Document	m	9.00	1690.00	Rupees One Thousand Six Hundred Ninety Only

Executive Engi
Project Divi
Yelahanka Zo

Contractor

	Item Name	Unit	Estimate Quantity	Rates quoted by Sri.C N S MURTHY	
				Rate in figures	Rate in words
233	Providing and fixing white vitreous china clay, water closet europeon type (pedestal type, p-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers. 10 litre low level,P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets , 40mm diameter flush pipe fittings and clamps, overflow arrangements with specials and 25mm mosquito proof coupling of approved design,painting of fittings and brackets, cutting and making good the wall and floor wherever required , including cost of materials, labour complete as per specifications. Specification no.KBS 11 ---- All terms and conditions are as per Tender Document	Each	19.00	5983.00	Rupees Five Thousand Nine Hundred Eighty Three Only
234	Providing and fixing white vitreous china clay,flat back or half stall urinal basin of size 580x380x350mm in the range of two with 7.5 litres P.V.C automatic flushing cistern, C.I / M.S brackets ,standard flush pipe and C.P brass spreaders with brass unions and G.I clamps, C.I trap with outlet grating and other couplings in C.P brass, painting of fittings and brackets, cutting and making good the wall and floor wherever required , including cost of materials, labour complete as per specifications. ---- All terms and conditions are as per Tender Document	Unit	4.00	9698.00	Rupees Nine Thousand Six Hundred Ninety Eight Only
235	Providing and fixing white vitreous china clay,flat back wash basin size 630x450mm with a pair of 15mm C.P brass pillar taps with C.I / M.S brackets ,32mm C.P brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required , including cost of materials, labour complete as per specifications. ---- All terms and conditions are as per Tender Document	Unit	13.00	4530.00	Rupees Four Thousand Five Hundred Thirty Only
236	Providing and fixing C.P brass towel rail 740mm length, 20mm dia with C.P brackets, fixed to wooden cleats with C.P brass screws including cost of materials, labour complete as per specifications. ---- All terms and conditions are as per Tender Document	Unit	2.00	912.00	Rupees Nine Hundred Twelve Only
237	Providing wash basin brackets of approved 1st qyuality and make confirming to ISI specifications and fixing for low down cistern as directed. Rate includes cost of materials and conveyance to work spot. ---- All terms and conditions are as per Tender Document	Pair	13.00	265.00	Rupees Two Hundred Sixty Five Only
238	Providing pedestal for wash basin of approved 1st qyuality and make confirming to ISI specifications and fixing for low down cistern as directed. Rate includes cost of materials and conveyance to work spot. ---- All terms and conditions are as per Tender Document	Each	13.00	1020.00	Rupees One Thousand Twenty Only
239	Providing and fixing 7.5 cms to 15.00 cms dia NP grating 100 mm dia. ---- All terms and conditions are as per Tender Document	Each	26.00	185.00	Rupees One Hundred Eighty Five Only
240	Providing stoneware gully trap of approved quality and make fixing in M-15 and plastering with CM 1:3 wherever necessary. (Rate includes cost of all materials, fixtures and lead). 15x15cms ---- All terms and conditions are as per Tender Document	Each	4.00	315.00	Rupees Three Hundred Fifteen Only
241	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials,labour charges, HOM of acquirements and testing complete as per specifications.For Rain water pipe. 110 mm dia ---- All terms and conditions are as per Tender Document	m	10.00	479.00	Rupees Four Hundred Seventy Nine Only
242	160mm dia ---- All terms and conditions are as per Tender Document	m	20.00	968.00	Rupees Nine Hundred Sixty Eight Only
243	Providing and fixing in position brass bib cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. ---- All terms and conditions are as per Tender Document	Each	2.00	282.00	Rupees Two Hundred Eighty Two Only
244	Providing and fixing in position brass stop cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. ---- All terms and conditions are as per Tender Document	Each	18.00	185.00	Rupees One Hundred Eighty Five Only

Executive Eng
Project D
Yelahanka

Contractor

	Item Name	Unit	Estimate Quantity	Rates quoted by Sri.C N S MURTHY	
				Rate in figures	Rate in words
	providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. ---- All terms and conditions are as per Tender Document	Each	2.00	475.00	Rupees Four Hundred Seventy Five Only
246	25mm dia nominal bore ---- All terms and conditions are as per Tender Document	Each	1.00	688.00	Rupees Six Hundred Eighty Eight Only
247	32mm nominal bore ---- All terms and conditions are as per Tender Document	Each	3.00	1108.00	Rupees One Thousand One Hundred Eight Only
248	40mm nominal bore ---- All terms and conditions are as per Tender Document	Each	2.00	1480.00	Rupees One Thousand Four Hundred Eighty Only
249	65mm nominal bore ---- All terms and conditions are as per Tender Document	Each	1.00	2985.00	Rupees Two Thousand Nine Hundred Eighty Five Only
250	Providing and fixing unplasticised PVC connection pipe with brass union 15mm nominal bore 300 mm length of PVC connection including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. ---- All terms and conditions are as per Tender Document	Set	12.00	307.00	Rupees Three Hundred Seven Only
251	Providing and fixing in position 40mm nominal bore non return valve vertical type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. --- All terms and conditions are as per Tender Document	Nos	2.00	1672.00	Rupees One Thousand Six Hundred Seventy Two Only
252	40mm dia ---- All terms and conditions are as per Tender Document	m	20.00	307.00	Rupees Three Hundred Seven Only
253	63mm dia ---- All terms and conditions are as per Tender Document	m	5.00	405.00	Rupees Four Hundred Five Only
254	Providing and placing on terrace, polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications. (For 1000 Litre capacity) as per IS 12701 1996. ---- All terms and conditions are as per Tender Document	Each	1.00	9875.00	Rupees Nine Thousand Eight Hundred Seventy Five Only
255	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for not and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.,) 15mm nominal OD pipes ---- All terms and conditions are as per Tender Document	m	2.00	151.00	Rupees One Hundred Fifty One Only
256	20mm nominal OD pipes ---- All terms and conditions are as per Tender Document	m	15.00	245.00	Rupees Two Hundred Forty Five Only
257	25mm nominal OD pipes ---- All terms and conditions are as per Tender Document	m	10.00	290.00	Rupees Two Hundred Ninety Only
258	32mm nominal OD pipes ---- All terms and conditions are as per Tender Document	m	20.00	360.00	Rupees Three Hundred Sixty Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone